

**Pandal, Stage , Interior/Exterior Decoration and Allied works for SARAS MELA 2018  
Municipal Ground, Pattambi, Palakkad**

SI No:	Description of work	No or Qty	Unit
<b>Appendix A- Civil Arrangements</b>			
1	Setting up and erecting up of weather proof/water proofPandal ( <b>Hanger Pandal with GI sheet and white sealing or semi circle Dome Pandal with nylon tarpaulin sheet</b> ) <b>with decoration works covered with all units including 234product stalls (26 stalls in a row –9 rows)</b> excluding stalls in Parking areaand all sides are covered in suitable partition board (acrylic/mica). The pandals should be provided with water proof/ weather proof roof covering(fixed with MS wire, coir yarn etc) and also provide wooden floor (using plywood laid 25 cm above the ground level with the support of small wooden post,with floor carpets) and the height of the pandal in centre portion is minimum 10-12 meter and side portion is minimum of 5-6 meter. Decoration work (Arches with decorative works/writings/designs) is to be providedas per the direction of the officials concerned with one major arche, one at the entrance of road leading to melaground and two small arches at the entrance and exit portions of the pandal. The pandal roofs should have GI pipe fixed to the top for preventing movement of roof and tying with M. S. wire , coir yarn etc( <b>Rate to be quoted seperatly for Hanger Pandal and Semi circle Dome Pandal ) (Mela Ground part II)</b> (loading and unloading included)	77.23 x 49.99	Meter
2	Setting up and erecting up of weather proof/water proofPandal ( <b>Hanger Pandal with GI sheet and white sealing</b> ) <b>with decoration works covered with all units including 12room for police aid post, office, media room, reception, fire force, first aid unit, VIP lounge and rest roometc,</b> and all sides are covered in suitable partition board (acrilic/mica). The pandals should be provided with water proof/ weather proof roof covering and also provide wooden floor, with floor carpets using plywood laid 25 cm above the ground level with the support of small wooden post, MS wire, coir yarn etc, and the height of the pandal in centre portion is minimum 4-5 meter. The pandal roofs should have GI pipe fixed to the top for preventing movement of roof and tying with M. S. wire , coir yarn etc( <b>Parking Ground</b> )(loading and unloading included)	45 x 10	Meter
3	Setting up and erecting up of weather proof/water proofpandal ( <b>Hanger Pandal with GI sheet and white sealing or semi circle Dome Pandal with nylon tarpaulin sheet</b> ) <b>with decoration works which will cover Programme Stage, Audience sitting area and Food Court area - Dining Area and cooking and display area etc,</b> and all sides are covered in suitable partition board (acrilic/mica). The pandals should be provided with water proof/ weather proof roof (fixed with MS wire, coir yarn etc) covering and also provide wooden floor, with floor carpets (excluding washing and cooking area) using plywood laid 25 cm above the ground level with the support of small wooden post, MS wire, coir yarn etc, and the height of the pandal in centre portion is minimum 10-12 meter and side portion is minimum of 5-6 meter. Decoration work is to be provided in the stage backdrop as per the direction of the officials concerned. This pandal should include necessary drainage of waste water with waste water collection pit and facility to remove food waste from time to time (every night). The pandal roofs should have GI pipe fixed to the top for preventing movement of roof and tying with M.	89.46 x 42	Meter

	S. wire , coir yarn etc( <b>Rate to be quoted separately for Hanger Pandal and Semi circle Dome Pandal ) (Mela Ground part I)</b> (loading and unloading included)		
4	Setting up and erecting <b>234 individual stalls/cubicles(26 stalls in a row –9 rows) inside the pandhal (under item 1 - Mela Ground part II)</b> , face to face (except one row) and each stall having minimum area of 3.0 x 3.0 sqm, with 3 sides covered with suitable partition board (acrylic/mica) with Passages of <b>4 meters</b> wide in between face-to-face stalls (with rope or metal rope divider fixed on the floor to avoid zig-zag movement of people to both sides) . Each stall/cubicle should be furnished with 2 tables and 2 numbers of chairs(armless) and should be electrified with 2 numbers of fluorescent tube, 1 number of 5 A plug.The stalls should be provided withboards for providing stall numbers and providing stall names or unit names.	234	Nos
5	Providing and setting up of wooden shelf (or metal) in the back side of each stall with the height of shelf is 1.50m and arranging 4-5 number of racks in this shelf a minimum width of 30cm.	125	Nos
6	Settingup water proof/weather proof <b>urinals /bathroom/toilet/latrines</b> furnished with buckets, jugs, and maintaining the same, by periodically sanitizing and disinfecting the same and supplying with continuous water supply and readymade septic tank facility, at the venue in consultation with officials concerned. (10 ladies toilets and 5 gents toilet)	15	Nos
7	Providing (loading and unloading included)and laying of <b>foldable tables</b> .	800	Nos
8	Providing (loading and unloading included)and laying of <b>cloths over the tables in offices</b> laid out.	200	Nos
9	Providing (loading and unloading included)and laying of <b>chairs with arms</b> .	100	Nos
10	Providing (loading and unloading included) and laying of <b>chairs without arms</b> .	650	Nos
11	Supplying (loading and unloading included) and erecting of <b>2 Syntex water tanks of 5000 litres</b> capacity erected on strong stands and setting up with continuous water supply to and from the water tanks to the kitchen/food court and toilets separately, and wherever necessary	2	Unit
12	Supplying (loading and unloading included) and erecting a storage tank/tanks with a total capacity of 10000 liters with motor and necessary plumbing arrangements at ground level near the raised syntex tank for continuous water supply	1	Unit
13	Providing and fixing plumbing lines of 25 mm pvc pipes to kitchen, toilet, etc	400	m
14	Supplying (loading and unloading included) and erectingof <b>hand wash basins of 8 numbers</b> on strong stands and providing the same with continuous water supply for washing and necessary drainage of the used water	2	set
15	Supplying with <b>water taps</b> with necessary plumbing and drainage arrangements.	10	nos
16	Supplying with <b>kitchen sinks</b> with necessary plumbing and drainage arrangements.	10	nos
17	Providing (loading and unloading included)and laying of <b>executive chairs with arms and cushions and seat covering</b> . (including VIP lounge)	20	Nos
18	Providing (loading and unloading included)and laying of <b>executive glass tables or teepoys</b> for stage area.	2	No
19	Providing (loading and unloading included)and laying of <b>wooden dias/podium</b> for stage area.	1	No
20	Setting up and erecting up of Stage 10 x 6 m with carpet and stage backdrop setting as per the direction of officials concerned (with a Green Room adjacent to it)	1	No

21	Setting up and erecting up of an Entrance Arch cum art work - specially designed Art Work (with materials such as wood, hard board, bamboo, cloth etc - (50 M long wall and Arch) along the Perinthalmanna – Pattambi Road, as per the direction of officials concerned – at the entrance of Parking ground (excluding the Arches in Unit 1)	1	No
22	Canopy 3.0 x 1.50 m (Food Court)	20	No
23	Coolers (Including VIP lounge, Office, Media, Stage)	10	No
24	Setting up and erecting of wooden staircase having 3-4 M length with suitable number of stairs at the exit portion of the Pandal – Unit 3 in the schedule / Mela Ground I, for exit from the Mela Ground to Market Road		
25	Necessary land levelling/filling works (with JCB) in the Parking ground with development of an earthen temporary approach slope way to Market road (strengthening the existing one for people to walk to Markert road from Parking ground). Necessary fencing with metal sheets around the Pandal (except entrance and exit portions). The fencing in the Front side of the Mela Ground to be covered with white cloth Necessary fencing in the Parking Ground between parking area and Fish Market area. Cleaning of bushes and other waste from Parking Ground, Market Road and the road connecting between Market Road and Bypass Road and from the road in front of/opposite to Mela Ground.		
<b>Appendix B- Electrical and Electronic Arrangements</b>			
26	Hire and labour charges for providing of <b>ceiling fans</b> of 1200 /1400 mm with suitable and safe wiring as per IS specifications and standards to all stalls, offices, stage, canteen, etc and giving connection	350	Nos
27	Hire and labour charges for providing of <b>Pedestal fans</b> with suitable and safe wiring as per IS specifications and standards to all stalls, offices, stage, canteen, etc and giving connection	50	Nos
28	Hire and labour charges for providing 1200 mm patties single tube fluorescent fitting with 40 W tube in position and connection as required as per IS specifications with suitable and insulated wiring to all stalls, offices, stage, canteen, open spaces inside pandal etc.	200	Nos
29	Providing and fixing of <b>85 W CFL lamps or equivalent</b> as per IS specifications with suitable and insulated wiring .	200	Nos
30	Hire and labour charges for providing of <b>400 W M H lamp or equivalent</b> and giving connection as required as per IS specifications with suitable and insulated wiring and necessary scaffolding .	100	Nos
31	Hire and labour charges for erecting and fixing of <b>lamp posts</b> firmly on ground with of 6 meters height above ground level at suitable intervals.	30	Nos
32	Hire and labour charges for providing and fixing of <b>halogen lamps of 1000 W</b> as per IS specifications with suitable and safe wiring .	6	Nos
33	Hire and labour charges for providing and fixing of <b>LED PARKENS LIGHT of 200 W</b> as per IS specifications with suitable and safe wiring .	20	Nos
34	Hire and labour charges for providing and fixing of <b>LED decorative/illumination lights</b> of strips with minimum 40 bulbs in each strip as per IS specifications with suitable and safe wiring .	300	strip
35	Hire and labour charges for providing DG set of required capacity with stand by and with operator for the complete period of operation.	2	Nos
36	Hire and labour charges for providing 15A plug point and giving connection with safe wiring and insulation as per Is	5	Nos

	standards and specifications as required.		
37	Hire and labour charges for providing 5A plug point and giving connection with safe wiring and insulation as per Is standards and specifications as required.	20	Nos
38	Hire and labour charges for providing 250 A main board with supply , 100 A outgoing HRC, MCB, fuses , change over facility with suitable size angle iron frame work and giving necessary connection to generator and KSEB supplies and earthing as per IS specifications and standards.	1	No
39	Hire and labour charges for providing ordinary type pipe earthings sufficient as per IS specifications and standards and giving connections etc. as required.	1	unit
40	Providing and connecting a codeless microphone as per IS specifications and standards.	3	Nos
41	Providing and connecting a wired microphone with stand as per IS specifications and standards.	2	Nos
42	Providing and connecting a stage monitor of 600 W as per IS specifications and standards.	2	No
43	Providing and fixing of loud speakers of 6000 W with amplifier, pre-amplifier, cd players with a minimum 30 channel mixer with proper earthing as per IS specifications and standards.	1	Unit
44	Providing and fixing additional boosters of 4000 W as per IS specifications and standards for inauguration and closing ceremonies.	2	days
45	Supplying and fixing printed flex boards with wooden frames /hanging type as per the direction.		
a	office boards of size 0.60 m x 0.30 m	25	Nos
b	direction boards of size 1.0 m x 0.50 m	25	Nos

**All the above should be erected/supplied/installed and handed over in working condition by 9:00 AM of March 28, 2018 and should be maintained till April 08, 2018. The pandals should be dismantled and the site to be cleared by April 10, 2018.**

1. Clearance to be obtained from PWD, Electrical Inspectorate and from Fire and Rescue Department, and any other Department as required, by the Contractor/Tenderer
2. Connection from KSEB should be obtained. The fees/charges paid for the inspection from the respective departments will be reimbursed once after producing the receipts of above payments.
3. GST / VAT will be charged/applicable as per Government of Kerala/India rules.
4. IT and welfare fund will be recovered as per Government norms.