

Out door Publicity / Electrical and Electronic Arrangements and Allied works for SARAS MELA 2018
Municipal Ground, Chengannur, Alappuzha

Sl. No	Out door Publicity and venue brandings	Size	Nos	Days	Unite Rate	Amount
1	Setting up and erecting up of an Entrance Arch with art work - specially designed Art Work with materials such as wood, hard board, bamboo, cloth etc -		1			
2	Welcome designer branded arches- Two arches at the entrance of the Exhibition and Food pandals.	2	2			
3	Coloured festoon with digital printing leading to the mela ground. 3 layer on both sides	lumpsum				
4	White cloth flag (3x6) with logo printed with approved art work. To be erected on poles on both sides to the mela ground		50			
Appendix B- Electrical and Electronic Arrangements						
1	Hire and labour charges for providing of ceiling fans of 1200 /1400 mm with suitable and safe wiring as per IS specifications and standards to all stalls, offices, stage, canteen, etc and giving connection		350			
2	Hire and labour charges for providing of Pedestal fans with suitable and safe wiring as per IS specifications and standards to all stalls, offices, stage, canteen, etc and giving connection	50	50			
3	Hire and labour charges for providing 1200 mm patties single tube fluorescent fitting with 40 W tube in position and connection as required as per IS specifications with suitable and insulated wiring to all stalls, offices, stage, canteen, open spaces inside pandal etc.		200			
4	Providing and fixing of 85 W CFL lamps or equivalent as per IS specifications with suitable and insulated wiring .		200			
5	Hire and labour charges for providing of 400 W M H lamp or equivalent and giving connection as required as per IS specifications with suitable and insulated wiring and necessary scaffolding .		100			
6	Hire and labour charges for erecting and fixing of lamp posts firmly on ground withof 6 meters height above ground level at suitable intervals.		30			
7	Hire and labour charges for providing and fixing of halogen lamps of 1000 W as per IS specifications with suitable and safe wiring .		10			
8	Hire and labour charges for providing and fixing of LED decorative/illumination lights of stripswith minimum 40 bulbs in each strip as per IS specifications with suitable and safe wiring .		300			
9	Coolers (Including VIP lounge, Office, Media, Stage)		10			
10	Hire and labour charges for providing DG set of required capacity with stand byand with operator for the complete period of operation. Including Fuel for 12 hrs / day. The contractor should provide necessary sound and light arrangements and power supply for the remaining time.		2			

11	Hire and labour charges for providing 15A plug point and giving connection with safe wiring and insulation as per IS standards and specifications as required.		10			
12	Hire and labour charges for providing 5A plug point and giving connection with safe wiring and insulation as per IS standards and specifications as required.		25			
13	Hire and labour charges for providing 250 A main board with supply , 100 A outgoing HRC, MCB, fuses , change over facility with suitable size angle iron frame work and giving necessary connection to generator and KSEB supplies and earthing as per IS specifications and standards.		1			
14	Hire and labour charges for providing ordinary type pipe earthings sufficient as per IS specifications and standards and giving connections etc. as required.		1			
15	Providing and fixing Sound system 6000 W for stalls and Entire venue announcement and channel musics including Technician		1			
16	Providing and fixing of loud speakers of 25000 W with amplifier, pre-amplifier, cd players with a minimum 30 channel mixer with proper earthing as per IS specifications and standards.	unit	1			
17	Providing and connecting a codeless microphone as per IS specifications and standards.		3			
18	Providing and connecting a wired microphone with stand as per IS specifications and standards.		2			
19	Providing and connecting a stage monitor of 600 W as per IS specifications and standards.		2			
20	Hire and labour charges for providing and fixing of Sharpy Lights as per IS specifications with suitable and safe wiring .		6			
21	Hire and labour charges for providing and fixing of LED PARKENS LIGHT of 200 W as per IS specifications with suitable and safe wiring .		30			
22	Hire and labour charges for providing and fixing of PARKENS LIGHT of 200 W as per IS specifications with suitable and safe wiring .		16			
23	Supplying and fixing printed flex boards with wooden frames /hanging type as per the direction.					
a	Office boards of size 0.60 m x 0.30 m		25			
b	Direction boards of size 1.0 m x 0.50 m		25			
	Total					
	Gst 18%					
	Grand Total					

All the above should be erected/supplied/installed and handed over in working condition by 9:00 AM of August 10, 2018 and should be maintained till August 23rd, 2018. The pandals should be dismantled and the site to be cleared by September 9th, 2018.

Clearance to be obtained from PWD, Electrical Inspectorate and from Fire and Rescue Department, and any other Department as required, by the Contractor/Tenderer

Connection / Sanction from KSEB should be obtained. The fees/charges paid for the inspection from the respective departments will be reimbursed once after producing the receipts of above payments.

GST / VAT will be charged/applicable as per Government of Kerala/India rules.

IT and welfare fund will be recovered as per Government norms.