

Pandal, Stage , Interior/Exterior Decoration and Allied works for SARAS MELA 2018  
Municipal Ground, Chengannur, Pathanamthitta

SI No:	Description of work	Size / Qty	Nos	Days	Sqft /Unite Rate	Amount
	<b>Super structure / Hanger Pandhal set up.</b>					
1	<p><b>Exhibition Pandhal.</b> Setting up and erecting up of weather proof/water proofPandal (Hanger Pandal with GI sheet and white sealing or semi circle Dome Pandal with nylon tarpaulin sheet) with decoration works covered with all units for 234 product stalls (22 stalls in a row – 10 rows) excluding stalls in Parking area and all sides are covered in suitable partition board (acrylic/mica). The pandals should be provided with water proof/ weather proof roof covering(fixed with MS wire, coir yarn etc) and also provide wooden floor (using plywood laid 25 cm above the ground level with the support of small wooden post,with floor carpets) and the height of the pandal in centre portion is minimum 6-8 mtr meter and side portion is minimum of 5-6 meter. The pandal roofs should have GI pipe fixed to the top for preventing movement of roof and tying with M. S. wire , coir yarn etc(Rate to be quoted seperatly for Hanger Pandal and Semi circle Dome Pandal ) (Mela Ground part II) (loading and unloading included)</p>	78 x 50	Meter			
2	<p><b>Multipurpose Utility Pandhal.</b> Setting up and erecting up of weather proof/water proofPandal (Hanger Pandal with GI sheet and white sealing) with decoration works covered with all units including 12room for police aid post, office, media room, reception, fire force, first aid unit, VIP lounge and rest room etc, and all sides are covered in suitable partition board (acrilic/mica). The pandals should be provided with water proof/ weather proof roof covering and also provide wooden floor, with floor carpets using plywood laid 25 cm above the ground level with the support of small wooden post, MS wire, coir yarn etc, and the height of the pandal in centre portion is minimum 4-5 meter. The pandal roofs should have GI pipe fixed to the top for preventing movement of roof and tying with M. S. wire , coir yarn etc(Parking Ground)(loading and unloading included)</p>	Basket ball court. 25 x 18	Meter			

3	<b>Food / Cultural Pandhal.</b> Setting up and erecting up of weather proof/water proofpandal (Hanger Pandal with GI sheet and white sealing or semi circle Dome Pandal with nylon tarpaulin sheet)with decoration works which will cover Programme Stage, Audience sitting area and Food Court area - Dining Area and cooking and display area etc, and all sides are covered in suitable partition board (acrilic/mica). The pandals should be provided with water proof/ weather proof roof (fixed with MS wire, coir yarn etc) covering and also provide wooden floor, with floor carpets (excluding washing and cooking area) using plywood laid 25 cm above the ground level with the support of small wooden post, MS wire, coir yarn etc, and the height of the pandal in centre portion is minimum 10-12 meter and side portion is minimum of 5-6 meter. Decoration work is to be provided in the stage backdrop as per the direction of the officials concerned. This pandal should include necessary drainage of waste water with waste water collection pit and facility to remove food waste from time to time (every night). The pandal roofs should have GI pipe fixed to the top for preventing movement of roof and tying with M.S. wire , coir yarn etc(Rate to be quoted separately for Hanger Pandal and Semi circle Dome Pandal ) (Mela Ground part I)(loading and unloading included)	73x25 60x6	Meter			
4	Setting up and erecting 234individual stalls/cubicles(22 stalls in a row –10 rows) inside the pandhal (under item 1 - Mela Ground part II), face to face (except one row) and each stall having minimum area of 3.0 x 3.0 sqm, with 3 sides covered with suitable partition board (acrilic/mica) with Passages of 4 meters wide in between face-to-face stalls (with rope or metal rope divider fixed on the floor to avoid zig-zag movement of people to both sides) . Each stall/cubicle should be furnished with 2 tables and 2 numbers of chairs(armless) and should be electrified with 2 numbers of fluorescent tube, 1 number of 5 A plug.The stalls should be provided withboards for providing stall numbers and providing stall names or unit names.	234	Nos			
5	Providing and setting up of wooden shelf (or metal) in the back side of each stall with the height of shelf is 1.50m and arranging 4-5 number of racks in this shelf a minimum width of 30cm. Neatly covered with white cloths	125	Nos			
6	Settingup water proof/weather proof urinals /bathroom/toilet/latrines furnished with buckets, jugs, and maintaining the same, by periodically sanitizing and disinfecting the same and supplying with continuous water supply and readymade septic tank facility, at the venue in consultation with officials concerned. (10 ladies toilets and 5 gents toilet)	15	Nos			
7	Providing (loading and unloading included) and laying of foldable tables .	300	Nos			
8	Providing Round Table with clothes and laying	40				
9	Providing Armless chairs with cover and laying for food court	300				
10	Providing (loading and unloading included) and laying of cloths over the tables in offices laid out.	200	Nos			
11	Providing (loading and unloading included)and laying of chairs with arms .	100	Nos			
12	Providing (loading and unloading included) and laying of chairs without arms .	650	Nos			
13	Fire Extinguisher ( Big )	10				

14	Supplying (loading and unloading included) and erecting of 2 Syntex water tanks of 5000 litres capacity erected on strong stands and setting up with continuous water supply to and from the water tanks to the kitchen/food court and toilets separately, and wherever necessary	2	Unit			
15	Supplying (loading and unloading included) and erecting a storage tank/tanks with a total capacity of 10000 liters with motor and necessary plumbing arrangements at ground level near the raised syntex tank for continuous water supply	1	Unit			
16	Providing and fixing plumbing lines of 25 mm pvc pipes to kitchen, toilet, etc	400	meter			
17	Supplying (loading and unloading included) and erecting of hand wash basins of 4 nos. of taps on strong stands and providing the same with continuous water supply for washing and necessary drainage of the used water	5	Set			
18	Supplying with water taps with necessary plumbing and drainage arrangements.	40	Nos			
19	Supplying with kitchen sinks with necessary plumbing and drainage arrangements.	14	Nos			
20	Providing (loading and unloading included) and laying of executive chairs with arms and cushions and seat covering . (including VIP lounge)	20	Nos			
21	Providing (loading and unloading included) and laying of executive glass tables or teepoys for stage area.	2	Nos			
22	Providing (loading and unloading included) and laying of wooden dias/podium for stage area.	1	Nos			
23	Setting up and erecting up of Stage 15 x 8 m with carpet and stage backdrop setting as per the direction of officials concerned (with a Green Room adjacent to it)	1	Nos			
24	Canopy 3.0 x 1.50 m (Food Court)	20	Nos			
25	Necessary land levelling/filling works (with JCB) in the Parking ground, Necessary fencing with metal sheets around the Pandals (except entrance and exit portions). Cleaning of bushes and other waste from Parking Ground, Mela ground and the road connecting between main Road Mela Ground.	lumpsum				
<b>Total</b>						
Gst 18%						
<b>Grand Total</b>						

All the above should be erected/supplied/installed and handed over in working condition by 9:00 AM of August 10, 2018 and should be maintained till August 23rd, 2018. The pandals should be dismantled and the site to be cleared by September 5th, 2018.

Clearance to be obtained from PWD, Electrical Inspectorate and from Fire and Rescue Department, and any other Department as required, by the Contractor/Tenderer

Connection / Sanction from KSEB should be obtained. The fees/charges paid for the inspection from the respective departments will be reimbursed once after producing the receipts of above payments.

GST / VAT will be charged/applicable as per Government of Kerala/India rules.

IT and welfare fund will be recovered as per Government norms.